

May 16, 2025

ADDENDUM TO ADVERTISED CONTRACT

PROJECT NAME: CITY OF DAWSONVILLE ROADWAY
REHABILITATION -FDR PROJECT

PROJECT NUMBER: PW-25-001

CITY: CITY OF DAWSONVILLE

AMENDMENT NUMBER: 3

LETTING DATE: MAY 21, 2025

THE FOLLOWING CHANGES ARE HEREBY MADE TO THIS CONTRACT. THE BIDDER IS RESPONSIBLE FOR MAKING ANY NECESSARY CHANGES IN INK IN THE PROPOSAL. BIDDER SHALL ACKNOWLEDGE THIS AMENDMENT BY CHECKING THE APPROPRIATE SPACE ON THE AMENDMENT CERTIFICATION PAGE.

.....

QUESTIONS/CLARIFICATIONS

1. If we are patching on Richmond Drive with 19mm and also using 19mm in Pearl Chambers Subdivision there isn't a way to differentiate between the 19mm used for patching and that on Pearl Chambers on the bid schedule. Typically there would be a patching line item separate so that the cost of milling and existing material can be included in the patching cost. Would you consider creating a separate bid item for patching? If not, could you tell us how many tons of patching is estimated so we can include that cost. **On page 49 of the bid docs, it shows the patching on Richmond Drive at 116 tons...it is mislabeled as 4" patching...it should be 2" patching using 19MM. There will be a pay item added for patching.**
2. **Revised bid scheduled attached**

PROJECT # PW-25-001

ROADWAY REHABILITATION - FDR

Contract Scope: Furnish all labor, materials and equipment necessary for 1.2 miles of roadway rehabilitation. All surplus material gets delivered to The City of Dawsonville Public Works Department at 716 Maple Street, Dawsonville, GA 30534

Vendor: _____

Signature: _____

BID SCHEDULE OF ITEMS

Line No.	Pay Item No.	Item	Approx QTY	Unit	Unit Price	Amount
5	150-1000	TRAFFIC CONTROL - INCL TEMP STRIPING	LS	1		
10	210-0200	GRADING PER MILE – DIRT SHLDR	LM	0.7		
15	315-1000	PORTLAND CEMENT -FDR	TN	202		
20	310-1080	10" CEMENT STABLIZED RECLAIMED BASE	SY	8567		
23	402-1802	RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H-LIME (220 LB/SY)	TN	116		
25	402-3102	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP 2, BLEND 1, INCL BITUM MATL & H LIME	TN	1287		
30	402-3190	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2 ONLY, INCL BITUM MATL & H LIME	TN	1471		
35	413-1000	BITUM TACK COAT	GL	3000		
40	432-0208	MILL ASPH CONC PVMt, 2" DEPTH	SY	8567		
45	432-0212	MILL ASPH CONC PVMt, 3" DEPTH	SY	4536		
50	432-5010	MILL ASPH CONC PVMt, VARIABLE DEPTH	SY	1832		
55	653-0120	THERMOPLASTIC PVMt MARKING, ARROW, TP 2	EA	2		
60	653-1502	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, YELLOW	LF	6600		
65	653-1501	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 IN, WHITE	LF	6600		
70	653-1704	THERMOPLASTIC SOLID TRAFFIC STRIPE, 24 IN, WHITE	LF	100		
75	654-1003	RAISED PVMt MARKERS TP 3	EA	620		
80	700	PERMANANET GRASSING - HYDROSEEDING INCL FERTIZILERS & LIME APPLICATION	AC	0.4		
TOTAL BID						

Signature/Firm _____