

July 15, 2026

ADDENDUM TO ADVERTISED CONTRACT

PROJECT NAME: CITY OF DAWSONVILLE ROADWAY
RESURFACING

PROJECT NUMBER: PW-26-02

CITY: CITY OF DAWSONVILLE

AMENDMENT NUMBER: 1

LETTING DATE: July 22, 2026

THE FOLLOWING CHANGES ARE HEREBY MADE TO THIS CONTRACT. THE BIDDER IS RESPONSIBLE FOR MAKING ANY NECESSARY CHANGES IN INK IN THE PROPOSAL. BIDDER SHALL ACKNOWLEDGE THIS AMENDMENT BY CHECKING THE APPROPRIATE SPACE ON THE AMENDMENT CERTIFICATION PAGE.

.....

QUESTIONS/CLARIFICATIONS

1. On the summary report, page 44 of the bid documents, Robinson Rd shows receiving 12.5MM topping. The detail on page 48 shows 9.5MM Topping. Which is correct? **The summary report is correct the typical section should say 12.5 MM. The 12.5 MM should be used for the heavy truck traffic on Robinson Road.**
2. There are several notes under scope of work that cover shoulder building, however Figuring the roadways are being full width milled the depth of the binder and topping, I assume shoulder building and grassing would not be necessary. Could the City please clarify whether or not shoulder building and grassing will be required? **Any shoulder building and/or grassing would be a minimal amount and the cost should be included in the overall bid.**
3. May advanced warning signage be placed on temporary tripod stands? **Advanced warning signage may be placed on temporary tripods.**

